

ECOLOGICAL SURVEY REPORT



**OHIO DEPARTMENT OF TRANSPORTATION
OFFICE OF ENVIRONMENTAL SERVICES
1980 WEST BOARD STREET
COLUMBUS, OHIO 43223
(614) 466-7100**



Project C-R-S / Name:	Opportunity Corridor
Project Identification Number (PID):	77333
Report Type:	Level Two ESR
Report Author(s):	/Debra E White/Kevin S Schroeder
Affiliation:	Michael Baker Jr., Inc.
Phone:	216-776-6612
Email:	dewwhite@mbakercorp.com/kschroeder@mbakercorp.com
Date of Submission:	January 5, 2010

TABLE OF CONTENTS	PAGE
PROJECT SUMMARY	1
LITERATURE REVIEW	2
FIELD METHODS	4
FIELD DATA COLLECTION RESULTS	5
Aquatic Ecology	5
Stream Table	5
Wetland Table	5
Potentially Jurisdictional Ditch Table	5, 6
Pond, Lake, Reservoir Table	5
Fish Community Table	5
Aquatic Macroinvertebrate Community Table	5
Mussel Community Table	5
Terrestrial Ecology	7
Vegetative Communities Table	8
Vegetation Table	9, 10
Mammal Table	11
Bird Table	12
Reptile Table	--
Amphibian Table	--
Listed Species	13
Federally Listed Species Table	14
State Listed Species Table	15
IMPACT SUMMARY	16
Streams Impacts	--
Wetland Impacts	--
Potentially Jurisdictional Ditch Impacts	17
Pond, Lake, Reservoir Impacts	--
Impacts to Aquatic Life	18
Vegetative Community Impacts	19
Impacts to Terrestrial Wildlife	20
Federally Endangered Indiana Bat (<i>Myotis sodalis</i>) Impacts	--
Federally Listed Species Impacts	--
State Listed Species Impacts	--
LITERATURE CITED	21
APPENDICES	22

PROJECT SUMMARY

Location Data

ODOT District:	District 12
County(ies):	Cuyahoga
Township(s):	
Project Center (lat./lon.):	41.486874 -81.628962
Study Area Size (Ac):	713 acres

Project Description

The Opportunity Corridor Study is investigating alternatives to improve the transportation infrastructure to support the City of Cleveland's goal to revive and redevelop large tracks of vacant residential and industrial land within the City of Cleveland's southeast side. The transportation infrastructure improvements are anticipated to begin near I-490 at East 55th Street at the southwest and terminate along East 105th Street near US-322 (Chester Avenue) at the northeast. The study area boundary has been approved by ODOT Central Office. The facility, as proposed, would be a multilane urban arterial boulevard constructed at existing street grade and include signalization at major intersections. Due to high traffic volumes, alternatives are being developed at East 55th Street for an at-grade and grade separated intersection. In addition grade separation structures are proposed for locations where the new roadway crosses the existing rail lines owned and operated by Norfolk Southern (NS) and Greater Cleveland Regional Transit Authority (GCRTA). Existing roadways that intersect the new boulevard would be widened, if necessary, to accommodate the proposed traffic volumes.

In addition to the No-build alternative, conceptual alignments are being developed within the current study area. In the vicinity of E55th Street alternatives are being further developed for both at grade and grade separated intersections. These alternatives are all envisioned to have impacts to the northern limits of the St. Hyacinth Neighborhood. The limits are generally limited to the area north of Francis Avenue. In the study area east of the St. Hyacinth Neighborhood to the existing E105th/Quincy Avenue intersection, the study area is bound by the GCRTA Red line/NS Nickel Plate line trench to the north, the overhead GCRTA Blue/Green line to the south, and the overhead CSX mainline to the east. The elevated NS mainline tracks bisect this area. West of the NS mainline the alternatives are generally east-west in nature and include the potential reuse and widening of Grand Avenue or a parallel route located 1-2 blocks further south in the vicinity of Rawlings Avenue. East of the NS mainline, the alignments generally proceed in a northeasterly direction toward the intersection of E105th Street and Quincy Avenue. Within this section of the study area, the alternatives are either on a completely new alignment or they will utilize a portion of existing Woodland Avenue. These alternatives include alignments both northeast and southwest of the existing Kenneth Johnson Recreation Center. North of Quincy Avenue the existing E105th Street corridor is common to each alternative; however, the alignments will consist of symmetric, eastern, and western widening of the existing roadway.

Ecological Impact Summary (Impacts may be preliminary and subject to revision)

Impacts may occur to potentially jurisdictional ditches. No other significant ecological impacts are anticipated from implementation of the proposed project.

LITERATURE REVIEW

Literature Source(s) Reviewed (check all that apply)		Results of Review	Map Included In Appendix
<input checked="" type="checkbox"/>	Land Cover Mapping	(list on Land Use/Cover Table)	YES
<input checked="" type="checkbox"/>	Ecoregion Map	List Ecoregion(s): 61a. Erie Lake Plain (Choose an Ecoregion)	NO
<input checked="" type="checkbox"/>	Geological Maps of Ohio	List Physiographic Region(s): 8.0 Erie Lake Plain (Choose Physiographic Region)	NO
<input checked="" type="checkbox"/>	USGS 7.5 Minute Topographic Quadrangle Maps	List quadrangle(s): <input type="text" value="Cleveland South"/> East Cleveland <input type="text" value="Shaker Heights"/>	YES
<input checked="" type="checkbox"/>	County Soil Survey	Mapped hydric soils within study area? YES Only soils with major hydric components.	YES
<input type="checkbox"/>	Ohio Water Quality Standards (Ohio Administrative Code, Chapter 3745-1)		Not Applicable
<input type="checkbox"/>	Biological and Water Quality Reports	List reports that cover study area (if applicable):	Not Applicable
<input checked="" type="checkbox"/>	Hydrologic Unit Code(s) (HUC)	List 14 Digit HUCs within study area: 04110002060050 & 04110003010010	YES
<input checked="" type="checkbox"/>	Total Maximum Daily Load (TMDL) Program	List TMDL status of study area (If applicable): Final report approved by USEPA / None	NO
<input checked="" type="checkbox"/>	National and State Wild and Scenic River lists, and the Nationwide Rivers Inventory (NRI)	List river(s) within or near the study area (if within applicable reach): Not Applicable (Choose River)	NO
<input checked="" type="checkbox"/>	Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps (FIRM)	Does the study area that lie within a 100 year floodplain: YES	YES
<input checked="" type="checkbox"/>	Ohio's Coastal Zone Management Area	Does the study area that lie within the Coastal Zone management Area: YES	NO
<input checked="" type="checkbox"/>	National Wetlands Inventory (NWI) and or Ohio Wetland Inventory Mapping (OWI)	OWI indicates shrub-scrub wetlands NWI indicates no wetlands	YES
<input checked="" type="checkbox"/>	ODNR Division of Natural Areas and Preserves Natural Heritage Database	Are there records for listed species within 1 mile of the study area? YES Summarize on State Listed Species Table	YES
<input checked="" type="checkbox"/>	Federally Endangered, Threatened, Proposed and Candidate Species in Ohio	List and Summarize on Federally Listed Species Table	YES

Land Use/Cover Table

List the Land Use/Cover types found within the study area (based on descriptions from NLCD ,2001):	Acres
Developed, Open Space - Includes areas with a mixture of some constructed materials, but mostly vegetation in the form of lawn grasses. Impervious surfaces account for less than 20% of total cover. (large-lot single-family housing units, parks, etc...)	39.8
Developed, Low Intensity - Includes areas with a mixture of constructed materials and vegetation. Impervious surfaces account for 20-49% of total cover. These areas most commonly include single-family housing units.	233.9
Developed, Medium Intensity - Includes areas with a mixture of constructed materials and vegetation. Impervious surfaces account for 50-79% of the total cover. These areas most commonly include single-family housing units.	298.2
Developed, High Intensity - Includes highly developed areas where people reside or work in high numbers. Examples include apartment complexes, row houses and commercial/industrial. Impervious surfaces account for 80 to 100% of the total cover.	141.5

FIELD METHODS

Field Investigator Name(s):	Debra E. White / Kevin S. Schroeder
Affiliation:	Michael Baker Jr., Inc.
Date(s) of Field Work:	October 5 - 7, 2009
Weather Conditions:	Mostly sunny, seasonably warm

Check All that apply

Stream Survey (Habitat and Biology)

- ☐ Field Evaluation Manual for Ohio's Primary Headwater Habitat Streams (v 1.0) (OEPA 2002)
- ☐ Methods for Assessing Habitat in Flowing Waters: Using the Qualitative Habitat Evaluation Index (QHEI). (OEPA 2006)
- ☐ Biological Criteria for the Protection of Aquatic Life: Volume I (OEPA 1987a), Volume II (OEPA 1987b, 2008a), Volume III (OEPA 1989, 2008b),
- ☒ ODOT Ecological Manual: Sections 203.2.3.1-Stream, 203.2.3.5-Fishes, 203.2.3.6-Macrobenthos, 203.2.3.7-Mussels (ODOT 2009)
- ☐ Other Methods (describe and cite):

Wetland Delineation and Classification

- ☒ Corps of Engineers Wetlands Delineation Manual. Technical Report Y-87-1 (Environmental Laboratory 1987)
 - Interim Regional Supplement to the Corps of Engineers Wetland Delineation Manual:
 - ☐ Midwest Region (Environmental Laboratory 2008)
 - ☐ Northcentral and Northeast
 - ☐ Eastern Mountains and Piedmont
- ☐ Classification of Wetlands and Deepwater Habitats of the United States (Cowardin et.al. 1979)
- ☐ Ohio Rapid Assessment Method for Wetlands v. 5.0, User's Manual and Scoring Forms (OEPA 2001)
- ☐ Other Methods (describe and cite):

Other Waters

- ☒ ODOT Ecological Manual: Sections 203.2.3.3-Ditches/Swales, 203.2.3.4-Ponds/Lakes (ODOT 2009)
- ☐ Other Methods (describe and cite):

Terrestrial

- ☒ ODOT Ecological Manual: Section 203.2.3.4-Terrestrial Ecology (ODOT 2009)
- ☐ Other Methods (describe and cite):

Listed Species

- ☒ ODOT Ecological Manual: Sections 203.2.3.5-Listed Species (ODOT 2009)
- ☐ Other Methods (describe and cite):

FIELD DATA COLLECTION RESULTS

Aquatic Ecology

Streams

Were any streams identified within the project study area? (If NO, delete the Stream Table)	NO
Total number of streams within the study area:	Enter Number
Total length of streams within the study area (linear feet):	Enter Length

Wetlands

Were any wetlands identified within the project study area? (If NO, delete the Wetland Table)	NO
Total number of wetlands within the study area:	Enter Number
Total area of wetlands within the study area (acres):	Enter Area

Potentially Jurisdictional Ditches

Were any potentially jurisdictional ditches identified within the project study area? (If NO, delete the Potentially Jurisdictional Ditch Table)	YES
Total number of potentially jurisdictional ditches within the study area:	3
Total area of potentially jurisdictional ditches within the study area (acres):	0.11

Ponds

Were any ponds identified within the project study area? (If NO, delete the Pond Table)	NO
Total number of ponds within the study area:	Enter Number
Total area of ponds within the study area (acres):	Enter Area

Aquatic Life

Were any fish communities sampled/observed within the project study area? (If NO, delete the Fish Table)	NO
If yes, total number of fish species identified:	Enter Number
Were any aquatic macroinvertebrate communities sampled/observed within the project study area? (If NO, delete the Macroinvertebrate Table)	NO
If yes, total number of aquatic macroinvertebrate species identified:	Enter Number
Were any mussel communities sampled/observed within the project study area? (If NO, delete the Mussel Table)	NO
If yes, total number of mussel species identified:	Enter Number

Potentially Jurisdictional Ditch Table										
(Warning: ditches that acquire/possess an ordinary high water mark and become relatively permanent waters outside of right-of-way (upstream) should be assessed as streams and included on the Stream Table)										
Ditch I.D.:	Photograph #(s):	Receiving Waters:	14-Digit HUC the Wetland is Located within (Code):	USACE Flow Characteristics:	OHWM Present:	Constructed Through or Drains a wetland:	Constructed Through a Mapped Hydric Soil Unit(s):	Flows Between Two or More Potential Waters of the US:	Average Width of Wetted Perimeter Within Study Area (ft.)	Total Length Within Study Area (lin. ft.):
A		Kingsbury Run	04110002060050	Relatively Permanent Water-Seasonal	NO	NO	NO Udorthents, loamy	NO	3	1,375
Additional Information. List How the ditch connects to a Traditional Navigable Water (TNW) and any other pertinent observations :			Ditch flows to a captured stream (i.e., Kingsbury Run) via underground storm pipes. See attached Figure 8.							
B		Kingsbury Run	04110002060050	Relatively Permanent Water-Seasonal	NO	NO	NO Udorthents, loamy	NO	3	156
Additional Information. List How the ditch connects to a Traditional Navigable Water (TNW) and any other pertinent observations :			Ditch flows to a captured stream (i.e., Kingsbury Run) via underground storm pipes. See attached Figure 8.							
C		Kingsbury Run	04110002060050	Relatively Permanent Water-Seasonal	NO	NO	NO Udorthents, loamy	NO	3	92
Additional Information. List How the ditch connects to a Traditional Navigable Water (TNW) and any other pertinent observations :			Ditch flows to a captured stream (i.e., Kingsbury Run) via underground storm pipes. See attached Figure 8.							

Terrestrial Ecology

Vegetative Communities

List the number of distinct vegetative communities identified within the study area	4
Were any unique or high quality terrestrial habitats identified within the study area?	NO

Terrestrial Wildlife

Were any mammals observed within the project study area? (If NO, delete the Mammal Table)	YES
If yes, total number of species identified:	2
Were any birds observed within the project study area? (If NO, delete the Bird Table)	YES
If yes, total number of bird species identified:	8
Were any reptiles observed within the project study area? (If NO, delete the Reptile Table)	NO
If yes, total number of reptile species identified:	Enter Number
Were any amphibian communities sampled/observed within the project study area? (If NO, delete the Amphibian Table)	NO
If yes, total number of amphibian species identified:	Enter Number

Vegetative Communities Table			
Vegetative Communities found within the study area:	Degree of Man Induced Ecological Disturbance (based on descriptions in Andreas et. al., 2004)	Unique, Rare, or High Quality?	Acres
Developed Open Space - DS - (mown right-of-way, large-lot single-family housing units, parks, golf courses, and vegetation planted in developed settings for recreation, erosion control, or aesthetic purposes)	Extreme Disturbance/Ruderal Community (dominated by opportunistic invaders or native highly tolerant taxa)	NO	N/A
Community Description (list dominant species, include Anderson (1982) community classification if applicable):	This is the dominant community type found within the study area. Dominant species include: common residential grasses (<i>Poaceae</i> spp.), common plantain (<i>Plantago major</i>), and clover (<i>Trifolium</i> spp.),		
Scrub/Shrub - SS - (true shrubs, and young trees in an early successional stage)	High Disturbance (dominated by widespread taxa not typical of a particular community)	NO	N/A
Community Description (list dominant species, include Anderson (1982) community classification if applicable):	These community types are found mostly adjacent to the rail lines that run through the middle of the study area. Dominant species include: European buckthorn (<i>Rhamnus cathartica</i>), staghorn sumac (<i>Rhus typhina</i>), honeylocust (<i>Gleditsia triacanthos</i>), box elder (<i>Acer negundo</i>), and grapes (<i>Vitis</i> spp.).		
Upland Forest - UF - (uplands dominated by trees)	Low Disturbance (dominated by plants with a narrow range of ecological tolerances that typify a stable or near "climax" community)	NO	N/A
Community Description (list dominant species, include Anderson (1982) community classification if applicable):	These upland forested areas are limited within the study area but are found on some of the steeper side slopes where development is difficult due to the steep terrain. Dominant species include: eastern cottonwood (<i>Populus deltoids</i>), northern catalpa (<i>Catalpa speciosa</i>), red maple (<i>Acer rubrum</i>), grapes (<i>Vitis</i> spp.), poison ivy (<i>Toxicodendron radicans</i>), and white wood aster (<i>Eurybia divaricata</i>).		
Grassland/Herbaceous - GH - (new fields, pastures, hay fields)	High Disturbance (dominated by widespread taxa not typical of a particular community)	NO	N/A
Community Description (list dominant species, include Anderson (1982) community classification if applicable):	This limited community type is found in areas that are transitioning from extremely disturbed conditions and are now vegetated in hardy opportunistic species, such as, ragweed (<i>Ambrosia artemisiifolia</i>), white snakeroot (<i>Ageratina altissima</i>), Queen Anne's lace (<i>Daucus carota</i>), Japanese knotweed (<i>Polygonum cuspidatum</i>), jumpseed (<i>Polygonum virginianum</i>), and Canada goldenrod (<i>Solidago Canadensis</i>).		

Vegetation Table						
Scientific Name:	Common Name:	C of C:	Indicator Status:	Federally Listed:	State Listed:	Location (use vegetative community codes):
<i>Poaceae</i> spp.	grasses		(Choose)	(Choose)	(Choose)	Developed Open Space
<i>Plantago major</i>	common plantain	*	FACU	NO	NO	Developed Open Space
<i>Trifolium</i> spp.)	clover		(Choose)	(Choose)	(Choose)	Developed Open Space
<i>Rhamnus cathartica</i>	European buckthorn	*	UPL	NO	NO	Scrub/Shrub - SS
<i>Rhus typhina</i>	staghorn sumac	2	UPL	NO	NO	Scrub/Shrub - SS
<i>Gleditsia triacanthos</i>	honeylocust	4	FAC	NO	NO	Scrub/Shrub - SS
<i>Acer negundo</i>	box elder	3	FAC	NO	NO	Scrub/Shrub - SS
<i>Populus deltoides</i>	eastern cottonwood	3	FAC	NO	NO	Upland Forest - UF
<i>Catalpa speciosa</i>	northern catalpa	*	FAC	NO	NO	Upland Forest - UF
<i>Acer rubrum</i>	red maple	2	FAC	NO	NO	Upland Forest - UF
<i>Acer saccharum</i>	sugar maple	5	FACU-	NO	NO	Upland Forest - UF
<i>Toxicodendron radicans</i>	poison ivy	1	FAC	NO	NO	Upland Forest - UF
<i>Vitis</i> spp.	grapes		(Choose)	NO	NO	Upland Forest - UF

<i>Platanus occidentalis</i>	American sycamore	7	FACW-	NO	NO	Upland Forest - UF
<i>Salix nigra</i>	black willow	2	FACW+	NO	NO	Upland Forest - UF
<i>Ambrosia artemisiifolia</i>	ragweed	0	FACU	NO	NO	Grassland/Herbaceous - GH
<i>Solidago rugosa</i>	wrinkleleaf goldenrod	2	FAC	NO	NO	Scrub/Shrub - SS
<i>Solidago canadensis</i>	Canada goldenrod	1	FACU	NO	NO	Grassland/Herbaceous - GH
<i>Euthamia graminifolia</i>	flat-topped goldenrod	2	FAC	NO	NO	Scrub/Shrub - SS
<i>Symphotrichum novae-angliae</i>	New England aster	2	FACW-	NO	NO	Scrub/Shrub - SS
<i>Symphotrichum ericoides</i>	white heath aster	2	FACU	NO	NO	Grassland/Herbaceous - GH
<i>Eurybia divaricata</i>	white wood aster	5	UPL	NO	NO	Upland Forest - UF
<i>Polygonum cuspidatum</i>	Japanese knotweed	*	FACU-	NO	NO	Scrub/Shrub - SS
<i>Polygonum virginianum</i>	jumpseed	3	FAC	NO	NO	Scrub/Shrub - SS
<i>Ageratina altissima</i>	white snakeroot	3	FACU-	NO	NO	Scrub/Shrub - SS
<i>Erigeron annuus</i>	daisy fleabane	0	FACU	NO	NO	Grassland/Herbaceous - GH
<i>Daucus carota</i>	Queen Anne's lace	*	UPL	NO	NO	Grassland/Herbaceous - GH
<i>Securigera varia</i>	crown vetch	*	UPL	NO	NO	Developed Open Space

General Mammal Discussion: Impacts to mammal species in the study area are not expected to be significant. Wildlife species that utilize the study area are comprised of species that are well adapted to the urban environment, highly mobile, and transient in nature. Upon completion of the Opportunity Corridor Project, many of these tolerant, opportunistic species will likely return to the Project Area.

Mice, voles, and rabbits are generally found at the bottom of the food chain in the upland habitat typical of the study area. Mammalian carnivores include feral dogs and cats. Omnivores found in the upland areas typically include squirrels, chipmunks, skunks, and raccoons.

Mammal Table			
Scientific Name	Common Name	Listing:	Location (use vegetative community codes):
<i>Peromyscus sp.</i>	mouse	Not Listed	Developed Open Space
<i>Tamias minimus</i>	least chipmunk	Not Listed	Developed Open Space

General Bird Discussion: Impacts to bird species in the study area are not expected to be significant. Birds that utilize the study area are comprised of species that are well adapted to the urban environment. Upon completion of the Opportunity Corridor Project, many of these tolerant, urban-adapted species will likely return to the Project Area. The bird species known to utilize these upland areas can be described as opportunistic and include species typical of disturbed urban environments. Bird carnivores such as hawks and buzzards thrive in this type of disturbed habitat, as well as many various songbirds.

Bird Table					
Scientific Name	Common Name	Date of Observation	Typical Ohio Range	Listing:	Location (use vegetative community codes):
<i>Zenaida macroura</i>	Mourning Dove	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space
<i>Corvus brachyrhynchos</i>	American crow	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space
<i>Junco hyemalis</i>	dark-eyed junco	10/7/2009	Winter Resident	Not Listed	Developed Open Space
<i>Turdus migratorius</i>	American robin	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space
<i>Poecile atricapilla</i>	black-capped chickadee	10/6/2009	Year-Round Resident	Not Listed	Upland Forest
<i>Sitta carolinensis</i>	white-breasted nuthatch	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space
<i>Passer domesticus</i>	house sparrow	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space
<i>Melospiza melodia</i>	song sparrow	10/5/2009	Year-Round Resident	Not Listed	Developed Open Space

Listed Species

Federally Listed Species

Were any federally listed species observed within the study area?	NO
Were any suitable habitats for federally listed species observed within the study area?	NO
Were any designated critical habitats for federally listed species present within the study area?	NO
Additional summary discussion on federally listed species:	

State Listed Species

Were any state listed species observed within 1 mile of the study area?	NO
Were any state listed species observed within the study area?	NO
Were any suitable habitats for state listed species observed within the study area?	NO
Additional summary discussion on state listed species:	

Federally Listed Species Table			
Scientific Name	Common Name	Listing	Write-up Including Impacts to Suitable Habitat (note designated critical habitat if present)
<i>(Myotis sodalis)</i>	Indiana Bat	Endangered	<p>After consultation with ODOT it was decided that the Indiana Bat Habitat Characterization Worksheet will not be necessary for this project.</p> <p>The study area is located within the urban area of the City of Cleveland in the Northeast Indiana Bat Management Unit. No hibernacula or records of captured bats were identified during DNAP's Natural Heritage Database search. The eastern border of the study area is near Rockefeller Park and Doan Brook's riparian corridor that under normal circumstances may provide a travel corridor used during migration. However, this corridor is surrounded by high intensity developed areas.</p>

State Listed Species Table			
Scientific Name	Common Name	Listing	Write-up Including Impacts to Suitable Habitat
Hieracium umbellatum	Canada hawkweed	Threatened	The location provided by the Natural Heritage Database is over one-half mile away from the project area. No populations of the Canada hawkweed were identified within the study area. No impacts to the Canada hawkweed or suitable habitat are anticipated by the project.
Falco peregrinus	peregrine falcon	Threatened	The location provided by the Natural Heritage Database appears to be a roof top. The peregrine falcon was not identified within or near the study area. No impacts to the peregrine falcon or suitable habitat are anticipated by the project.

IMPACT SUMMARY

Streams Impacts

Will any streams be impacted by the project? (If NO, delete the Stream Impact Table)	NO
Total number of streams impacted by the project (list multiple alignments separately):	Enter Number
Total length of streams impacted by the project (feet):	Enter Area

Potentially Jurisdictional Ditch Impacts

Will any potentially jurisdictional ditches be impacted by the project? (If NO, delete the Potentially Jurisdictional Ditch Impact Table)	YES
Total number of potentially jurisdictional ditches impacted by the project:	3
Total area of potentially jurisdictional ditches impacted by the project (acres):	0.11

Potentially Jurisdictional Ditch Impacts Table			Alternative Impacts (ac)
Ditch ID	Receiving Waters	USACE Flow Characteristics	Alternative 1
A	Kingsbury Run (a captured stream)	Relatively Permanent Water- Seasonal	0.09
Discussion of Impacts:			
B	Kingsbury Run (a captured stream)	Relatively Permanent Water- Seasonal	0.01
Discussion of Impacts:			
C	Kingsbury Run (a captured stream)	Relatively Permanent Water- Seasonal	0.01
Discussion of Impacts:			
Total Impact			0.11

Impacts to Aquatic Life

Discuss the types of habitat alternations that may result from construction activities (i.e. siltation, substrate modifications, banks shaping, channel relocation, etc...):

No impact to aquatic life habitat is expected from implementation of the proposed project, since no habitat exists. The potentially jurisdictional ditches are seasonal and contain no aquatic life or habitat.

Discuss the expected duration of the impacts (temporary/short term or permanent/long-term):

Any unexpected impacts to the ditches and their receiving waters will be temporary during the construction phase of the project. It should be noted that the receiving waters (i.e., Kingsbury Run) is currently captured underground and provides no habitat or functional use for aquatic life.

Discuss if the project impacts would result in the likely extirpation of any taxa from the area:

N/A

Include a general discussion of impacts to aquatic fauna (fish, mussels, aquatic macroinvertebrates):

N/A

Vegetative Community Impacts

Will any vegetative communities be impacted by the project? (If NO, delete the Vegetative Community Impact Table)	YES
Total number of vegetative communities impacted by the project:	Enter Number
Total area of vegetative communities impacted by the project (acres):	4
Describe any impacts to rare or unique vegetative communities:	
N/A	

Vegetative Community Impact Table			Alternative Impacts (ac)
Vegetative Community	Disturbance Level	Unique, Rare, or High Quality	Alternative 1
Developed Open Space - DS	Extreme Disturbance/Ruderal Community	NO	This study does not include alternatives, thus impacts are not calculated at this time.
Discussion of Impacts: The majority of the study area includes extremely disturbed ruderal community land; thus, impacts to this type community type (in regard to the ecosystem) shall be considered minimal.			
Scrub/Shrub - SS	High Disturbance	NO	This study does not include alternatives, thus impacts are not calculated at this time.
Discussion of Impacts: This highly disturbed community type is located adjacent to the existing rail lines that traverse through the project area. These areas lack diversity and provide little habitat to residential wildlife. In addition, the wildlife that utilizes this habitat community can easily relocate.			
Upland Forest - UF	Low Disturbance	NO	This study does not include alternatives, thus impacts are not calculated at this time.
Discussion of Impacts: These community types have been avoided by past construction/development activities due to these communities being located in areas of steep slopes. Avoidance of these areas for the implementation of this project will likely occur, as well.			
Grassland/Herbaceous - GH	High Disturbance	NO	This study does not include alternatives, thus impacts are not calculated at this time.
Discussion of Impacts: This highly disturbed community type is located in transitional areas that have either been left fallow or limited of restoration has been applied. These areas lack diversity and provide little habitat to residential wildlife. The wildlife that inhabits this habitat community can easily relocate.			

Impacts to Terrestrial Wildlife

Discuss any terrestrial habitat alternations that may result from construction activities:

Any terrestrial habitat alternations to occur as a result of the project shall be considered minimum based on the types and ecological disturbance that exists throughout the study area.

Discuss the expected duration of the impacts (temporary/short term or permanent/long-term):

The duration of impacts to terrestrial habitat shall be considered temporary; that is, until the wildlife relocates itself. Permanent impacts will occur but the available habitat is low quality and extremely disturbed.

Discuss if the project impacts would result in the likely extirpation of any taxa from the area:

N/A

Include a general discussion of impacts to terrestrial fauna (mammals, birds, reptiles, and amphibians):

Any of impacts to terrestrial fauna shall be considered minimal since the wildlife that utilizes the available habitat can easily relocate.

LITERATURE CITED

- Andreas, B. K., J.J Mack, and J.S. McCormac. 2004. Floristic Quality Assessment Index (FQAI) for vascular plants and mosses for the State of Ohio. Ohio Environmental Protection Agency, Division of Surface Water, Wetland Ecology Group, Columbus, Ohio. 219 p.
- Cowardin, L. M., V. Carter, F.C. Golet, and E. T. LaRoe. 1979. Classification of Wetlands and Deepwater Habitats of the United States. U.S. Fish and Wildlife Service. Biological Services Program Rept. FWS/OBS-79/31. 103 p.
- Environmental Laboratory. 1987. Corps of Engineers Wetlands Delineation Manual. Technical Report Y-87-1, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Environmental Laboratory. 2008. Interim Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region. ERDC/EL TR-08-27, U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- Ohio Department of Transportation (ODOT). 2009. Ecological Manual.
- Ohio Environmental Protection Agency (OEPA). 1987a. Biological Criteria for the Protection of Aquatic Life: Volume I, The Role of Biological Data in Water Quality Assessment. Division of Water Quality Monitoring and Assessment, Surface Water Section, Columbus, OH.
- _____. 1987b. Biological Criteria for the Protection of Aquatic Life: Volume II, Users Manual for Biological Field Assessment of Ohio Surface Waters. Division of Water Quality Monitoring and Assessment, Surface Water Section, Columbus, OH.
- _____. 1989. Biological Criteria for the Protection of Aquatic Life: Volume III, Standardized Biological Field Sampling and Laboratory Methods for Assessing Fish and Macroinvertebrate Communities. Division of Water Quality Monitoring and Assessment, Surface Water Section, Columbus, OH.
- _____. 2001. Ohio Rapid Assessment Method for Wetlands v. 5.0, User's Manual and Scoring Forms. Ohio EPA Technical Report WET/2001-1. Ohio EPA, Division of Surface Water. Columbus, Ohio.
- _____. 2002. Field Evaluation Manual for Ohio's Primary Headwater Habitat Streams (v 1.0). Ohio EPA, Division of Surface Water. Columbus, Ohio.
- _____. 2006. Methods for Assessing Habitat in Flowing Waters: Using the Qualitative Habitat Evaluation Index (QHEI). OHIO EPA Technical Bulletin EAS/2006-06-1. Ecological Assessment Section, Division of Surface Water Groveport, OH.
- _____. 2008a. Updates to Biological Criteria for the Protection of Aquatic Life: Volume II and Volume II Addendum. Users Manual for Biological Field Assessment of Ohio Surface Waters. Ecological Assessment Section, Division of Surface Water Groveport, OH.
- _____. 2008b. Updates to Biological Criteria for the Protection of Aquatic Life: Volume III. Standardized Biological Field Sampling and Laboratory Methods for Assessing Fish and Macroinvertebrate Communities. Ecological Assessment Section, Division of Surface Water Groveport, OH.

APPENDICES

A - Figures

- ☒ Project Location Mapping (Figure 1 and Figure 1A)
- ☒ Literature Review Mapping Results (Figure 2 through Figure 7)
- ☒ Ecological Resource Mapping (Figure 8)
- ☐ Other (List):

B - Photographs

- ☒ Photograph Location Map
- ☒ Photographs

C - Data Forms


- ☐ Stream Characterization/Assessment Data Forms
- ☐ Wetland Characterization/Assessment Data Forms
- ☐ Indiana Bat Habitat Characterization Worksheet
- ☐ Other (List):


D – Agency Data Requests

- ☒ ODNR, Division of Natural Areas and Preserves – Natural Heritage Database Information Request
- ☐ USFWS – Federally Listed Species Information Request
- ☐ Other (List):


APPENDIX A

FIGURES






Soil Map—Cuyahoga County, Ohio
(Opportunity Corridor)



Map Scale: 1:18,500 if printed on B size (11" x 17") sheet.



Web Soil Survey
National Cooperative Soil Survey

FIGURE 3

OPPORTUNITY CORRIDOR
Soil Map



Director 11 - Cleveland
3300 Avenue
Cleveland, Ohio 44115-2202
Phone: 216.398.1234
Fax: 216.398.1235
Email: d11@osu.edu





LEGEND

- 100 Year Floodplains
- Study Limits

500 0 500 1000 Feet




FIGURE 4


OPPORTUNITY CORRIDOR
100 Year Floodplains


Baker




District 12 - Cleveland
Metro Area

2017-2018
2019-2020
2020-2021
2021-2022
2022-2023
2023-2024
2024-2025
2025-2026
2026-2027
2027-2028
2028-2029
2029-2030
2030-2031
2031-2032
2032-2033
2033-2034
2034-2035
2035-2036
2036-2037
2037-2038
2038-2039
2039-2040
2040-2041
2041-2042
2042-2043
2043-2044
2044-2045
2045-2046
2046-2047
2047-2048
2048-2049
2049-2050
2050-2051
2051-2052
2052-2053
2053-2054
2054-2055
2055-2056
2056-2057
2057-2058
2058-2059
2059-2060
2060-2061
2061-2062
2062-2063
2063-2064
2064-2065
2065-2066
2066-2067
2067-2068
2068-2069
2069-2070
2070-2071
2071-2072
2072-2073
2073-2074
2074-2075
2075-2076
2076-2077
2077-2078
2078-2079
2079-2080
2080-2081
2081-2082
2082-2083
2083-2084
2084-2085
2085-2086
2086-2087
2087-2088
2088-2089
2089-2090
2090-2091
2091-2092
2092-2093
2093-2094
2094-2095
2095-2096
2096-2097
2097-2098
2098-2099
2099-2100
2100-2101
2101-2102
2102-2103
2103-2104
2104-2105
2105-2106
2106-2107
2107-2108
2108-2109
2109-2110
2110-2111
2111-2112
2112-2113
2113-2114
2114-2115
2115-2116
2116-2117
2117-2118
2118-2119
2119-2120
2120-2121
2121-2122
2122-2123
2123-2124
2124-2125
2125-2126
2126-2127
2127-2128
2128-2129
2129-2130
2130-2131
2131-2132
2132-2133
2133-2134
2134-2135
2135-2136
2136-2137
2137-2138
2138-2139
2139-2140
2140-2141
2141-2142
2142-2143
2143-2144
2144-2145
2145-2146
2146-2147
2147-2148
2148-2149
2149-2150
2150-2151
2151-2152
2152-2153
2153-2154
2154-2155
2155-2156
2156-2157
2157-2158
2158-2159
2159-2160
2160-2161
2161-2162
2162-2163
2163-2164
2164-2165
2165-2166
2166-2167
2167-2168
2168-2169
2169-2170
2170-2171
2171-2172
2172-2173
2173-2174
2174-2175
2175-2176
2176-2177
2177-2178
2178-2179
2179-2180
2180-2181
2181-2182
2182-2183
2183-2184
2184-2185
2185-2186
2186-2187
2187-2188
2188-2189
2189-2190
2190-2191
2191-2192
2192-2193
2193-2194
2194-2195
2195-2196
2196-2197
2197-2198
2198-2199
2199-2200
2200-2201
2201-2202
2202-2203
2203-2204
2204-2205
2205-2206
2206-2207
2207-2208
2208-2209
2209-2210
2210-2211
2211-2212
2212-2213
2213-2214
2214-2215
2215-2216
2216-2217
2217-2218
2218-2219
2219-2220
2220-2221
2221-2222
2222-2223
2223-2224
2224-2225
2225-2226
2226-2227
2227-2228
2228-2229
2229-2230
2230-2231
2231-2232
2232-2233
2233-2234
2234-2235
2235-2236
2236-2237
2237-2238
2238-2239
2239-2240
2240-2241
2241-2242
2242-2243
2243-2244
2244-2245
2245-2246
2246-2247
2247-2248
2248-2249
2249-2250
2250-2251
2251-2252
2252-2253
2253-2254
2254-2255
2255-2256
2256-2257
2257-2258
2258-2259
2259-2260
2260-2261
2261-2262
2262-2263
2263-2264
2264-2265
2265-2266
2266-2267
2267-2268
2268-2269
2269-2270
2270-2271
2271-2272
2272-2273
2273-2274
2274-2275
2275-2276
2276-2277
2277-2278
2278-2279
2279-2280
2280-2281
2281-2282
2282-2283
2283-2284
2284-2285
2285-2286
2286-2287
2287-2288
2288-2289
2289-2290
2290-2291
2291-2292
2292-2293
2293-2294
2294-2295
2295-2296
2296-2297
2297-2298
2298-2299
2299-2300
2300-2301
2301-2302
2302-2303
2303-2304
2304-2305
2305-2306
2306-2307
2307-2308
2308-2309
2309-2310
2310-2311
2311-2312
2312-2313
2313-2314
2314-2315
2315-2316
2316-2317
2317-2318
2318-2319
2319-2320
2320-2321
2321-2322
2322-2323
2323-2324
2324-2325
2325-2326
2326-2327
2327-2328
2328-2329
2329-2330
2330-2331
2331-2332
2332-2333
2333-2334
2334-2335
2335-2336
2336-2337
2337-2338
2338-2339
2339-2340
2340-2341
2341-2342
2342-2343
2343-2344
2344-2345
2345-2346
2346-2347
2347-2348
2348-2349
2349-2350
2350-2351
2351-2352
2352-2353
2353-2354
2354-2355
2355-2356
2356-2357
2357-2358
2358-2359
2359-2360
2360-2361
2361-2362
2362-2363
2363-2364
2364-2365
2365-2366
2366-2367
2367-2368
2368-2369
2369-2370
2370-2371
2371-2372
2372-2373
2373-2374
2374-2375
2375-2376
2376-2377
2377-2378
2378-2379
2379-2380
2380-2381
2381-2382
2382-2383
2383-2384
2384-2385
2385-2386
2386-2387
2387-2388
2388-2389
2389-2390
2390-2391
2391-2392
2392-2393
2393-2394
2394-2395
2395-2396
2396-2397
2397-2398
2398-2399
2399-2400
2400-2401
2401-2402
2402-2403
2403-2404
2404-2405
2405-2406
2406-2407
2407-2408
2408-2409
2409-2410
2410-2411
2411-2412
2412-2413
2413-2414
2414-2415
2415-2416
2416-2417
2417-2418
2418-2419
2419-2420
2420-2421
2421-2422
2422-2423
2423-2424
2424-2425
2425-2426
2426-2427
2427-2428
2428-2429
2429-2430
2430-2431
2431-2432
2432-2433
2433-2434
2434-2435
2435-2436
2436-2437
2437-2438
2438-2439
2439-2440
2440-2441
2441-2442
2442-2443
2443-2444
2444-2445
2445-2446
2446-2447
2447-2448
2448-2449
2449-2450
2450-2451
2451-2452
2452-2453
2453-2454
2454-2455
2455-2456
2456-2457
2457-2458
2458-2459
2459-2460
2460-2461
2461-2462
2462-2463
2463-2464
2464-2465
2465-2466
2466-2467
2467-2468
2468-2469
2469-2470
2470-2471
2471-2472
2472-2473
2473-2474
2474-2475
2475-2476
2476-2477
2477-2478
2478-2479
2479-2480
2480-2481
2481-2482
2482-2483
2483-2484
2484-2485
2485-2486
2486-2487
2487-2488
2488-2489
2489-2490
2490-2491
2491-2492
2492-2493
2493-2494
2494-2495
2495-2496
2496-2497
2497-2498
2498-2499
2499-2500
2500-2501
2501-2502
2502-2503
2503-2504
2504-2505
2505-2506
2506-2507
2507-2508
2508-2509
2509-2510
2510-2511
2511-2512
2512-2513
2513-2514
2514-2515
2515-2516
2516-2517
2517-2518
2518-2519
2519-2520
2520-2521
2521-2522
2522-2523
2523-2524
2524-2525
2525-2526
2526-2527
2527-2528
2528-2529
2529-2530
2530-2531
2531-2532
2532-2533
2533-2534
2534-2535
2535-2536
2536-2537
2537-2538
2538-2539
2539-2540
2540-2541
2541-2542
2542-2543
2543-2544
2544-2545
2545-2546
2546-2547
2547-2548
2548-2549
2549-2550
2550-2551
2551-2552
2552-2553
2553-2554
2554-2555
2555-2556
2556-2557
2557-2558
2558-2559
2559-2560
2560-2561
2561-2562
2562-2563
2563-2564
2564-2565
2565-2566
2566-2567
2567-2568
2568-2569
2569-2570
2570-2571
2571-2572
2572-2573
2573-2574
2574-2575
2575-2576
2576-2577
2577-2578
2578-2579
2579-2580
2580-2581
2581-2582
2582-2583
2583-2584
2584-2585
2585-2586
2586-2587
2587-2588
2588-2589
2589-2590
2590-2591
2591-2592
2592-2593
2593-2594
2594-2595
2595-2596
2596-2597
2597-2598
2598-2599
2599-2600
2600-2601
2601-2602
2602-2603
2603-2604
2604-2605
2605-2606
2606-2607
2607-2608
2608-2609
2609-2610
2610-2611
2611-2612
2612-2613
2613-2614
2614-2615
2615-2616
2616-2617
2617-2618
2618-2619
2619-2620
2620-2621
2621-2622
2622-2623
2623-2624
2624-2625
2625-2626
2626-2627
2627-2628
2628-2629
2629-2630
2630-2631
2631-2632
2632-2633
2633-2634
2634-2635
2635-2636
2636-2637
2637-2638
2638-2639
2639-2640
2640-2641
2641-2642
2642-2643
2643-2644
2644-2645
2645-2646
2646-2647
2647-2648
2648-2649
2649-2650
2650-2651
2651-2652
2652-2653
2653-2654
2654-2655
2655-2656
2656-2657
2657-2658
2658-2659
2659-2660
2660-2661
2661-2662
2662-2663
2663-2664
2664-2665
2665-2666
2666-2667
2667-2668
2668-2669
2669-2670
2670-2671
2671-2672
2672-2673
2673-2674
2674-2675
2675-2676
2676-2677
2677-2678
2678-2679
2679-2680
2680-2681
2681-2682
2682-2683
2683-2684
2684-2685
2685-2686
2686-2687
2687-2688
2688-2689
2689-2690
2690-2691
2691-2692
2692-2693
2693-2694
2694-2695
2695-2696
2696-2697
2697-2698
2698-2699
2699-2700
2700-2701
2701-2702
2702-2703
2703-2704
2704-2705
2705-2706
2706-2707
2707-2708
2708-2709
2709-2710
2710-2711
2711-2712
2712-2713
2713-2714
2714-2715
2715-2716
2716-2717
2717-2718
2718-2719
2719-2720
2720-2721
2721-2722
2722-2723
2723-2724
2724-2725
2725-2726
2726-2727
2727-2728
2728-2729
2729-2730
2730-2731
2731-2732
2732-2733
2733-2734
2734-2735
2735-2736
2736-2737
2737-2738
2738-2739
2739-2740
2740-2741
2741-2742
2742-2743
2743-2744
2744-2745
2745-2746
2746-2747
2747-2748
2748-2749
2749-2750
2750-2751
2751-2752
2752-2753
2753-2754
2754-2755
2755-2756
2756-2757
2757-2758
2758-2759
2759-2760
2760-2761
2761-2762
2762-2763
2763-2764
2764-2765
2765-2766
2766-2767
2767-2768
2768-2769
2769-2770
2770-2771
2771-2772
2772-2773
2773-2774
2774-2775
2775-2776
2776-2777
2777-2778
2778-2779
2779-2780
2780-2781
2781-2782
2782-2783
2783-2784
2784-2785
2785-2786
2786-2787
2787-2788
2788-2789
2789-2790
2790-2791
2791-2792
2792-2793
2793-2794
2794-2795
2795-2796
2796-2797
2797-2798
2798-2799
2799-2800
2800-2801
2801-2802
2802-2803
2803-2804
2804-2805
2805-2806
2806-2807
2807-2808
2808-2809
2809-2810
2810-2811
2811-2812
2812-2813
2813-2814
2814-2815
2815-2816
2816-2817
2817-2818
2818-2819
2819-2820
2820-2821
2821-2822
2822-2823
2823-2824
2824-2825
2825-2826
2826-2827
2827-2828
2828-2829
2829-2830
2830-2831
2831-2832
2832-2833
2833-2834
2834-2835
2835-2836
2836-2837
2837-2838
2838-2839
2839-2840
2840-2841
2841-2842
2842-2843
2843-2844
2844-2845
2845-2846
2846-2847
2847-2848
2848-2849
2849-2850
2850-2851
2851-2852
2852-2853
2853-2854
2854-2855
2855-2856
2856-2857
2857-2858
2858-2859
2859-2860
2860-2861
2861-2862
2862-2863
2863-2864
2864-2865
2865-2866
2866-2867
2867-2868
2868-2869
2869-2870
2870-2871
2871-2872
2872-2873
2873-2874
2874-2875
2875-2876
2876-2877
2877-2878
2878-2879
2879-2880
2880-2881
2881-2882
2882-2883
2883-2884
2884-2885
2885-2886
2886-2887
2887-2888
2888-2889
2889-2890
2890-2891
2891-2892
2892-2893
2893-2894
2894-2895
2895-2896
2896-2897
2897-2898
2898-2899
2899-2900
2900-2901
2901-2902
2902-2903
2903-2904
2904-2905
2905-2906
2906-2907
2907-2908
2908-2909
2909-2910
2910-2911
2911-2912
2912-2913
2913-2914
2914-2915
2915-2916
2916-2917
2917-2918
2918-2919
2919-2920
2920-2921
2921-2922
2922-2923
2923-2924
2924-2925
2925-2926
2926-2927
2927-2928
2928-2929
2929-2930
2930-2931
2931-2932
2932-2933
2933-2934
2934-2935
2935-2936
2936-2937
2937-2938
2938-2939
2939-2940
2940-2941
2941-2942
2942-2943
2943-2944
2944-2945
2945-2946
2946-2947
2947-2948
2948-2949
2949-2950
2950-2951
2951-2952
2952-2953
2953-2954
2954-2955
2955-2956
2956-2957
2957-2958
2958-2959
2959-2960
2960-2961
2961-2962
2962-2963
2963-2964
2964-2965
2965-2966
2966-2967
2967-2968
2968-2969
2969-2970
2970-2971
2971-2972
2972-2973
2973-2974
2974-2975
2975-2976
2976-2977
2977-2978
2978-2979
2979-2980
2980-2981
2981-2982
2982-2983
2983-2984
2984-2985
2985-2986
2986-2987
2987-2988
2988-2989
2989-2990
2990-2991
2991-2992
2992-2993
2993-2994
2994-2995
2995-2996
2996-2997
2997-2998
2998-2999
2999-3000
3000-3001
3001-3002
3002-3003
3003-3004
3004-3005
3005-3006
3006-3007
3007-3008
3008-3009
3009-3010
3010-3011
3011-3012
3012-3013
3013-3014
3014-3015
3015-3016
3016-3017
3017-3018
3018-3019
3019-3020
3020-3021
3021-3022
3022-3023
3023-3024
3024-3025
3025-3026
3026-3027
3027-3028
3028-3029
3029-3030
3030-3031
3031-3032
3032-3033
3033-3034
3034-3035
3035-3036
3036-3037
3037-3038
3038-3039
3039-3040
3040-3041
3041-3042
3042-3043
3043-3044
3044-3045
3045-3046
3046-3047
3047-3048
3048-3049
3049-3050
3050-3051
3051-3052
3052-3053
3053-3054
3054-3055
3055-3056
3056-3057
3057-3058
3058-3059
3059-3060
3060-3061
3061-3062
3062-3063
3063-3064
3064-3065
3065-3066
3066-3067
3067-3068
3068-3069
3069-3070
3070-3071
3071-3072
3072-3073
3073-3074
3074-3075
3075-3076
3076-3077
3077-3078
3078-3079
3079-3080
3080-3081
3081-3082
3082-3083
3083-3084
3084-3085
3085-3086
3086





APPENDIX B
PHOTOGRAPHS



FIGURE

OPPORTUNITY CORRIDOR
Ecological Resources
Photo Log

Baker

District 12-Cleveland
Metro Area



Photo 1: East facing view along GCRTA tracks at west end of the project area.



Photo 2: East facing view at west end of the project area showing a typical scrub-shrub community.



Photo 3: East facing view of potentially jurisdictional Ditch A which feeds Kingsbury Run (a captured stream) located on GCRTA property.



Photo 4: South facing view of potentially jurisdictional Ditch A.



Photo 5: West facing view of culvert located at potentially jurisdictional Ditch B on GCRTA property.



Photo 6: South facing view of scrub-shrub community located within the infield of GCRTA loop near potentially jurisdictional Ditch C.



Photo 7: East facing view of Norfolk Southern main line at Kinsman Road with upland forested community in the background.



Photo 8: Southeast facing view of Norfolk Southern and GCRTA lines located at Kinsman Road.



Photo 9: Northeast facing view from Berwick Road showing low intensity developed space and vegetation typical of the middle portion of the project area, including small tracts of upland forest and maintained residential grasses.



Photo 10: South facing view of open space with mature trees sparsely growing along Holton Avenue.



Photo 11: West facing view along Holton Avenue showing a mix of grass, shrubs, and trees.



Photo 12: North facing view of low density development in the background.



Photo 13: Southwest view along Grand Avenue showing overgrown scrub-shrub vegetation typical of the project area located adjacent to the rail lines.



Photo 14: Southwest facing view (toward East 79th Street) along the Norfolk Southern rail corridor that traverses through the center of the project area.



Photo 15: West facing view from Sherman Court towards railroad corridor showing typical vacant land located within the project area.



Photo 16: South facing view at Quincy Avenue and East 105th Street showing developed areas with newly vegetated grassland in the foreground.



Photo 17: Northeast facing view of railroad corridor at Quincy Avenue and East 105th Street.

APPENDIX C
DATA FORMS
(N/A)

APPENDIX D
AGENCY CORRESPONDENCE



Ohio Department of Natural Resources

TED STRICKLAND, GOVERNOR

SEAN D. LOGAN, DIRECTOR

Division of Natural Areas and Preserves

Anthony J. Celebreeze, III, Acting Chief

2045 Morse Rd., Bldg. F-1

Columbus, OH 43229-6693

Phone: (614) 265-6453; Fax: (614) 267-3096

September 29, 2009

Debra White
Michael Baker Jr., Inc.
1228 Euclid Ave., Suite 1050
Cleveland, OH 44115

Ms. White:

I have reviewed our Natural Heritage maps and files for the CUY-Opportunity Corridor project area, including a one mile radius, from I-490 to E. 105th St. in Cleveland, Cuyahoga County, and on the East Cleveland, Cleveland South and Shaker Heights Quads (119732). The numbers/letters on the list below correspond to the areas marked on the accompanying map. Common name, scientific name and status are given for each species.

Cleveland North/East Cleveland/Cleveland South/Shaker Heights Quads

A. Rockefeller Park - City of Cleveland

1. *Falco peregrinus* - Peregrine Falcon, threatened
2. Cave or Cavern
3. *Hieracium umbellatum* - Canada Hawkweed, threatened
4. *Falco peregrinus* - Peregrine Falcon, threatened

There are no dedicated state nature preserves or scenic rivers at the project site. We are unaware of any animal assemblages, state parks, state forests or state wildlife areas within a one mile radius of the project area. We also have no records for Indiana Bat (*Myotis sodalis*, state endangered, federal endangered) capture locations within a five mile radius or hibernacula within a ten mile radius of the project site.

Our inventory program has not completely surveyed Ohio and relies on information supplied by many individuals and organizations. Therefore, a lack of records for any particular area is not a statement that rare species or unique features are absent from that area. Please note that although we inventory all types of plant communities, we only maintain records on the highest quality areas.

Please contact me at 614-265-6818 if I can be of further assistance.


Sincerely,

A handwritten signature in blue ink, which appears to read "Debbie Woischke".

Debbie Woischke, Ecological Analyst
Natural Heritage Program



Cleveland North, East Cleveland,
Cleveland South & Shaker Heights
Quads, Cuyahoga Co.





Ohio Department of Natural Resources

TED STRICKLAND, GOVERNOR

SEAN D. LOGAN, DIRECTOR

Division of Natural Areas and Preserves

Anthony J. Celebreeze, III, Acting Chief

2045 Morse Rd., Bldg. F-1

Columbus, OH 43229-6693

Phone: (614) 265-6453; Fax: (614) 267-3096

September 29, 2009

Debra White
Michael Baker Jr., Inc.
1228 Euclid Ave., Suite 1050
Cleveland, OH 44115

Ms. White:

Per your request, I have e-mailed you a set of ArcView shape files with our Natural Heritage Database records for the CUY-Opportunity Corridor project ('data') in Cuyahoga County, and on the East Cleveland, Cleveland South and Shaker Heights Quads (project #119732). The files are projected in NAD83 Ohio State Plane South. The units are feet. This data will not be published or distributed beyond the scope of the project description on the data request form without prior written permission of the Natural Heritage Program.

Records included may be for rare and endangered plants and animals, geologic features, high quality plant communities and animal assemblages. Fields included are scientific and common names, state and federal statuses, as well as managed area and date of the most recent observation. State and federal statuses are defined as: E = endangered, T = threatened, P = potentially threatened, SC = species of concern, SI = special interest, FE = federal endangered, FT = federal threatened and A=recently added to inventory, status not yet determined.

Also included is a layer for managed areas ('ma') which includes state nature preserves, state parks, state forests and state wildlife areas, national wildlife refuges, county metro parks, as well as sites owned by non-profit groups (such as The Nature Conservancy), museums (such as the Cleveland Museum of Natural History), and others. Please be aware that the managed areas layer may not be complete. We are continually updating this layer as additional information becomes available to us.

I have also performed a search for Indiana Bat (*Myotis sodalis*, state endangered, federal endangered) capture sites within a five mile radius and hibernacula within a ten mile radius. If any records were found, this layer will be included and labeled "ib".

Our inventory program has not completely surveyed Ohio and relies on information supplied by many individuals and organizations. Therefore, a lack of records for any particular area is not a statement that rare species or unique features are absent from that area. Please note that although we inventory all types of plant communities, we only maintain records on the highest quality areas.

Please contact me at 614-265-6818 if I can be of further assistance.

Sincerely,

A handwritten signature in purple ink, which appears to read "Debbie Woischke".

Debbie Woischke, Ecological Analyst
Natural Heritage Program



Woischke, Debbie

From: Woischke, Debbie
Sent: Tuesday, September 29, 2009 1:21 PM
To: 'White, Debra'
Subject: Natural Heritage Data, 119732

Ms. White:

Per your request, I have e-mailed you a set of ArcView shape files with our Natural Heritage Database records for the CUY-Opportunity Corridor project ('data') in Cuyahoga County, and on the East Cleveland, Cleveland South and Shaker Heights Quads (project #119732). The files are projected in NAD83 Ohio State Plane South. The units are feet. This data will not be published or distributed beyond the scope of the project description on the data request form without prior written permission of the Natural Heritage Program.

Records included may be for rare and endangered plants and animals, geologic features, high quality plant communities and animal assemblages. Fields included are scientific and common names, state and federal statuses, as well as managed area and date of the most recent observation. State and federal statuses are defined as: E = endangered, T = threatened, P = potentially threatened, SC = species of concern, SI = special interest, FE = federal endangered, FT = federal threatened and A=recently added to inventory, status not yet determined.

Also included is a layer for managed areas ('ma') which includes state nature preserves, state parks, state forests and state wildlife areas, national wildlife refuges, county metro parks, as well as sites owned by non-profit groups (such as The Nature Conservancy), museums (such as the Cleveland Museum of Natural History), and others. Please be aware that the managed areas layer may not be complete. We are continually updating this layer as additional information becomes available to us.

I have also performed a search for Indiana Bat (*Myotis sodalis*, state endangered, federal endangered) capture sites within a five mile radius and hibernacula within a ten mile radius. If any records were found, this layer will be included and labeled "ib".

Our inventory program has not completely surveyed Ohio and relies on information supplied by many individuals and organizations. Therefore, a lack of records for any particular area is not a statement that rare species or unique features are absent from that area. Please note that although we inventory all types of plant communities, we only maintain records on the highest quality areas.

Per your request, I have also performed a manual search for this project. That letter and map will be mailed along with a hard copy of this letter and the invoice. Please contact me at 614-265-6818 if I can be of further assistance.



ma.shx (3 KB)



data.dbf (6 KB)



data.sbn (3 KB)



data.sbx (3 KB)



data.shp (4 KB)



data.shx (3 KB)



ma.dbf (3 KB)



ma.sbn (3 KB)



ma.sbx (3 KB)



ma.shp (5 KB)

Debbie Woischke, Data Specialist
Ohio Department of Natural Resources
Division of Natural Areas & Preserves
Natural Heritage Program
2045 Morse Rd., Bldg. F-1
Columbus, OH 43229
(phone) 614-265-6818
(fax) 614-267-3096